

Sequoia High School November 01, 2017






Agenda

- Caltrain System Overview
- Project Overview
- Electric Multiple Unit (EMU) Design
- Redwood City and North Fair Oaks Construction Activities
- Questions





Caltrain System



- 32 Stations Gilroy to San Francisco
- 92 Weekday Trains
- At-Grade Crossings, viaducts, and bridges
- Intermodal Connections
- Bike Commuters










Ridership



Cal train



At Capacity Today








Bi-directional commute with riders standing on trains going southbound and northbound





Aging Fleet

SERIES	QUANTITY	NUMBER OF SEATS	YEAR OF MANUFACTURE	MAKE	RETIRE DATE
Locamotives					
F40 PH-2	5	na	1985	GM - EMD	2015
F40PH-2-CAT	15	na	1985-1987	GM - EMD	2015-2017
F40 PH-2C	3	na	1998	Boise Locomotive	2028
MP36PH-3C	6	na	2003	Motive Power	2033
Passenger Cars					
Gallery Trailer	26	142	1985-1987	Nippon Sharyo	2015-2017
Gallery Trailer	16	148	1985-1987	Nippon Sharyo	2015-2017
Gallery Trailer	14	120	1999-2000	Nippon Sharyo	2030
Gallery Cab (Bike)	10	108	1985-1987	Nippon Sharyo	2015-2017
Gallery Cab (Bike)	6	78	1999-2000	Nippon Sharyo	2030
Gallery Cab (Bike)	21	97	1985	Nippon Sharyo	2015
Bi-Level Trailer*	16	149	1997	Bombardier	2027
Bi-Level Trailer	9	144	2002	Bombardier	2032
Bi-level Trailer (Bike)	2	114	2002	Bombardier	2032
Bi-level Trailer (Bike)	5	114	2001-2002	Bombardier	2031-2032
Bi-level Trailer (Bike)	2	114	2008	Bombardier	2038
Bi-level Trailer (Bike)	1	127	2002	Bombardier	2032
Bi-Level Trailer	6	140	2008	Bombardier	2038









Project Description


Area	Project	Service
51 miles	Electrification:	Up to 79 mph
San Francisco to San Jose (Tamien Station)	Overhead Contact System (OCS) Traction Power Facilities Electric Trains (EMUs) 75 percent of fleet	Service Increase • 6 trains / hour / direction • More station stops / reduced travel time • Restore Atherton & Broadway service Mixed-fleet service (interim period) Continue tenant service • ACE, Capital Corridor, Amtrak, Freight







Key Regional Benefits (2040)



Note: 2013 BAC Report, generates \$2.5B economic activity and 9,600 jobs







Schedule

MILESTONES



Please keep in mind that testing and construction will overlap as each Segment will be tested individually, prior to final system testing

Note: Schedule Subject to Change







Peninsula Corridor Electrification Project





Electric Train Outreach: Phased


- 2016 Capacity Board Decision (bike to seat ratio, onboard bathrooms, upper doors)
- 2017 Design Progressing: Additional Public Input
 - 2018 Virtual Reality 360 Tour







Electric Train Exterior Design Public Poll



Cal train



Electric Train Exterior Design

WINNING DESIGN: OPTION 1









Electric Train Seat Design





Caltrain



Electric Train Onboard Bike Storage Outreach





Electric Train Onboard Bike Storage Outreach

FEEDBACK COLLECTION PROCESS




Electric Train Onboard Bike Storage Design



- Maximizes capacity
- Accommodates variety of bike types
- · Recommended by:
 - Bicycle Advisory Committee
 - Bike Coalitions (SF and Silicon Valley)



















Work Segment 2, Area 1

- Redwood City
- North Fair Oaks









Field Work Status

Work Completed to	Utility Survey	
Date	Geotechnical Investigations	
	Disposal of Soil from Geotechnical Investigations	
	Soil Resistivity Testing	
	Site Surveys	
	Signal Cable Inspections	
Work In Progress	OCS Foundation Potholing	
and Upcoming	Signal Cable Potholing	
	Tree Pruning and Removal	
	OCS Foundation Construction	
Future Work	OCS Pole Installation	
	OCS Wire Installation	







Potholing













Future Construction Activities

Redwood City and North Fair Oaks

Date	Work Activity	Expected Duration
Late 2017/Early 2018	Tree Pruning/Removal	1-2 months
Summer 2018	Foundation Construction	3-4 months
Late 2018	Overhead Wiring Pole and Wire Installation	3-4 months








Tree Pruning and Replacement

Vegetation cleared for Electrical Safety Zone








Redwood City: Tree Pruning and Replacement Plan

City of Redwood City			
	Caltrain Right of Way	Private Property	Public Property
Trees Removed	16	0	2
Trees Pruned >25%	4	6	6
Trees Pruned <25%	28	7	37





North Fair Oaks: Tree Pruning and Replacement Plan

North Fair Oaks			
	Caltrain Right of Way	Private Property	Public Property
Trees Removed	17	13	0
Trees Pruned >25%	1	29	3
Trees Pruned <25%	55	11	12



Note: Information may change as the design progresses cal train



Foundation Work

- Excavation
- Rebar and Anchor Installation
- Electrical Grounding
- Concrete Fill







Foundation Specifics

- Approx. 130 poles installed in Redwood City
- Approx. 80 poles in North Fair Oaks
- Foundation size varies from 30" to 42"
- Foundation spacing approx. 180' apart





Pole Foundation Work

Will take place on and off track



DrillTech on track foundation train



DrillTech off-track OCS Drill Rig







Pole Installation



On/off-track crane for installation



Wide flange & square poles





Overhead Contact System (OCS)

Will take place on-track











Construction Impacts

- Daytime work and night work from 8 p.m.- 6 a.m.
- Some 24 hour weekend work
- Crews will utilize acoustical barrier blankets and position lights away from homes
- Dedicated hotline for construction complaints







Public Outreach


- Subscribe to Weekly Updates
 - Visit caltrain.com/pcepconstruction
- Additional Community Meetings
 - Pole and Wire Installation
- Construction Outreach Office







Public Outreach





Construction Contact Information

Email:calmod@caltrain.com

Phone: 650.399.9659 Toll Free: 800.660.4287

2121 S. El Camino Real, Suite A-100 San Mateo, CA 94403 9 a.m. - 6 p.m. Monday-Friday

www.caltrain.com/pcepconstruction



