



CALTRAIN CEMOF MODIFICATIONS/ ELECTRIFICATION UPDATE

San Jose Community Meeting July 24, 2019






AGENDA

- Caltrain System Overview
- Electrification Project Overview
- CEMOF Modifications Project Overview
- Questions





CALTRAIN SYSTEM



- 32 Stations Gilroy to San Francisco
- 92 Weekday Trains
- At-Grade Crossings, Viaducts, and Bridges
- Intermodal Connections
- Bike Commuters






PROJECT DESCRIPTION

Project Area



- 51 miles
- San Francisco to San Jose (Tamien Station)

Project Elements



Electrification

- Overhead Contact System (OCS)
- Traction Power Facilities

Electric Trains*

- 19 7-car train sets
- 133 electric cars

*Includes 2018 State TIRCP Funding





PROJECT DESCRIPTION

Service Elements



Speed

Up to 79 mph



Service Increase

- 6 trains / hour / direction
- More station stops / reduced travel time
- Restore Atherton & Broadway service



Mixed-fleet Service (interim period)

Continue Tenant Service

 ACE, Capitol Corridor, Amtrak, Freight





PROJECT BENEFITS



Improved Train
Performance,
Increased Service
and Greater Capacity



Improved Regional Air Quality and Reduced Greenhouse Gas Emissions



Positive Economic Benefits for the Region



Reduced Engine
Noise Emanating
from Trains




Increased Revenue and Reduced Fuel Cost





SCHEDULE

MILESTONES




*Please keep in mind that testing and construction will overlap as each Segment will be tested individually, prior to final system testing.

* Note: Schedule subject to change





CONSTRUCTION PHASING




- 51 Miles Corridor
- 4 Work Segments
- 3,000 Poles
- 10 Traction Power Facilities







SAN JOSE







FIELD WORK PROGRESSION

Work Completed	Utility Survey
	Geotechnical Investigations
	Disposal of Soil from Geotechnical Investigations
	Soil Resistivity Testing
	Site Surveys
	Signal Cable Inspections
Work In Progress	Tree Pruning/Removal
	Potholing
	Foundation Installation
	Traction Power Substation Construction
	Paralleling Station Construction
Future Work	CEMOF Facilities Modifications
	Signal House Construction
	Pole Installation
	Wire Installation





CONSTRUCTION SCHEDULE

San Jose

Date	Work Activity	Expected Duration*
In Progress	Potholing	2-3 months
In Progress	Foundation Construction	4-5 months
In Progress	Traction Power Substation Construction	6-9 months
In Progress	Paralleling Station Construction	3-4 months
August 2019	CEMOF Facility Modifications	9-12 months
Fall 2019	Pole/Wire Installation	3-4 months






FOUNDATION CONSTRUCTION


- Excavation
- Rebar and Anchor Installation
- Electrical Grounding
- Concrete Fill





FOUNDATION INSTALLATION









POLE INFORMATION

- 3,000 Installed throughout Corridor
 - Approx. 460 poles in San Jose
- Pole Height: 30-50'
- Pole Spacing: ~180' apart





POLE TYPES SAN JOSE



Single Track Cantilever



Two Track Cantilever




Center





POLE TYPES SAN JOSE






Portal

Headspan





POLE INSTALLATION







STRINGING WIRE








TRACTION POWER FACILITIES

- 10 Traction Power Facilities Installed throughout Corridor
 - 1 Traction Power Substation Installed in San Jose
 - 1 Paralleling Station in San Jose
 - Gantry structures up to 50'
- Provides electrical power to trains through the Overhead Contact System
- Unmanned station
- Day and weekend construction work
- Limited night work during construction






TRACTION POWER SUBSTATION LOCATION








TRACTION POWER SUBSTATION







PARALLELING STATION LOCATION







EXAMPLE PARALLELING STATIONS










TEST TRACK LOCATION







TEST TRACK INFORMATION

- Approximately 1.5 miles of existing maintenance track (no new track)
- Located between Santa Clara Station and Caltrain CEMOF facility
- Foundations, poles and wires to be installed prior to electric train testing
- New Electric trains will be tested on track
- Testing to begin in Spring 2020
- Testing anticipated to be during daytime





CEMOF BACKGROUND

- Central
 Equipment &
 Maintenance
 Facility (CEMOF)
- Completed in 2007
- Serves as the "nerve center" of Caltrain








CEMOF MODIFICATIONS

- Inspection Pit Extension
 - Enable workers to work underneath new electric trains
 - Extend 330 ft
- Other on-site improvements
 - Rolling Maintenance Platform (in building)
 - Camera installation
 - Temporary Parts storage building
- Expected Construction ~ 6 months











INSPECTION PIT




• Lengthen 330 ft





OTHER MODIFICATIONS



Electric train parts storage structure

Maintenance platform (within structure)





TEMPORARY BUILDING EXAMPLE





Cal Mod

CEMOF CONSTRUCTION INFORMATION

- Work hours typically weekdays from 7 a.m. to 5 p.m.
- Excavated dirt to be stored on-site
- Concrete trucks in area
 - Accessing facility from Stockton St. and Lenzen Ave.
- Sheet pile installation to act as a retention system to support excavation






GENERAL CONSTRUCTION INFORMATION

- Work will occur during day and night
- Some 24 hour weekend work
- Crews will utilize acoustical barrier blankets and position lights away from homes
- Dedicated hotline for construction complaints





PUBLIC OUTREACH



Cal Mod

CALTRAIN MODERNIZATION PROGRAM

Test Pile Construction Activities

DAY TIME WORK

08/28/17 - 09/1/17

ANTICIPATED WORK HOURS 7:00 a.m. - 5:00 p.m.

CREWS CONDUCTING WORK IN YOUR AREA TO INSTALL AND TEST FOUNDATION PILES

During the week of August 28, Caltrain electrification crews will be working in your area to construct one test pile foundation for integrity testing. The piles will be installed within the Caltrain right-of-way.

Crews will be conducting the work over a two day period between Monday, August 28 and Friday, September 1, between the hours of 7 a.m. and 5 p.m. Crews will return at a later date to test the integrity of the installed piles.

Main construction activities include:

- Survey and layout of proposed pile test location
- Trucks and equipment working near Caltrain right of way
- Drill holes for placement of test piles
- · Pour concrete and install rebar
- · Backfill holes to cover work areas


We spologize for any inconvenience this may cause. The field team will work as quietly as possible. Thank you for your patience and understanding as we deliver these critical benefits to our communities.

Please visit our website at www.caltrain.com/PCEPconstruction to sign-up for weekly construction updates.

We appreciate your patience during construction.



Doorhanger





Postcard



Public Meeting





PUBLIC OUTREACH

- Subscribe to Weekly Updates
 - Visit www.calmod.org/get-involved
- Social Media
- Construction Outreach Office





WHAT'S NEXT

- Caltrain Business Plan
 - Caltrain2040.org
- High-Speed Rail Blended System
 - hsr.ca.gov
- Caltrain Downtown Extension
 - sftca.org/transbay-transit-center
- Diridon Concept Plan
 - DiridonSJ.org





CALMOD CONTACT INFORMATION

WEEKLY UPDATES (a) CalMod.org/get-involved

PHONE () 650-399-9659 800-660-4287 (Toll Free)

OFFICE ② 2121 S. El Camino, Suite A-100 San Mateo, CA 94403

WEBSITE @ CalMod.org

FACEBOOK (1) www.facebook.com/caltrain

TWITTER ② @caltrain

