



City of Palo Alto **Grade Separation Project** Churchill Avenue, Meadow Drive, and Charleston Road

Palo Alto Community Meetings
August 25 and 26, 2026



CITY OF
PALO ALTO



Near-term Safety Improvements

Caltrain is committed to continuing our strong partnership with the City of Palo Alto to advance safety improvements that benefit the community.

Across Palo Alto/Alma, Churchill, Meadow and Charleston:

- Installed delineators, solar markers, pavement markings, and updated striping
- Implemented anti-trespass panel and Rail Sentry safety pilots





Welcome

30 Minutes



Welcome

Project Team Introductions
Project Presentation

30 Minutes



Q&A

Key Topics Q&A
Open Q&A

60 Minutes



Open House

Churchill Grade Crossing
Station
Meadow/Charleston Grade
Crossing Station

Both community meetings (August 25 and 26) cover the same content



Ways to Provide Input



**Comment
Cards**



**Project Website
Comment Form**




**Live Q&A
Session**

Translation services are provided through *Wordly*



Current Project Phase



Project Area





What We Heard

- Prior to 15% Design, we asked for your feedback on the alternatives; that input helped inform City Council's December direction
- Your comments are documented, tracked, and reported to Rail Committee and City Council

Recurring Themes from Community Feedback



Traffic and
circulation



Bicycle and
pedestrian safety



Student safety
and school access



Project Footprint



Aesthetics and
neighborhood character



Construction
impacts



Cost and
funding



Meeting Objectives



Share Project 15% Design




Describe Total Project Cost and Schedule Development Process



Outline the 35% Design and Environmental Phase



Direction from City Council






Design Process

Topic	15% Provided	35% Design Will Provide
Layout	Drawings of track profiles, roadways, intersection geometry, and paths	Refined profiles, intersection geometry, and bike and pedestrian facility design
Footprint	Preliminary project footprint for environmental studies	Established project footprint for approvals
Risks	Identified key risks, constraints, and constructability considerations	Preliminary utility depths verified through potholing, preliminary conflict matrix developed
Construction	Initial feasibility construction approach and sequencing	Updated construction approach and sequencing
Cost and Schedule	Independent Rough Order of Magnitude (ROM) total project cost estimate and schedule	Preliminary total project cost estimate and schedule

PARTIAL
UNDERPASS



Churchill Ave – *Partial Underpass*





Churchill Ave – *Partial Underpass*



Churchill Ave

Alma St


Alma St

Churchill Ave

Palo
Alto
High
School



Seale Ave – Bicycle and Pedestrian Undercrossing



Project footprint updated to accommodate utilities

Bicycle and pedestrian ramp to undercrossing

Driveway access maintained

Bicycle and pedestrian ramp to undercrossing

Bicycle and pedestrian routes to nearby schools

Alma St lanes shifted west to accommodate ramp

Refining box-jacking strategy for underpass



Seale Ave – Bicycle and Pedestrian Undercrossing



Ramp to/from
Undercrossing

Ramp to/from
Undercrossing

Castilleja Ave


Seale Ave

Alma St

Peers Park



Charleston Road – Underpass



Relocated bicycle and pedestrian ramp to Charleston Rd to enable utility relocation

Refining bicycle movements on east side of crossing

Ramps to lower intersection (signalized)

Bicycle and pedestrian bridge over Charleston Rd

At-grade railroad bridge

Ramp to lower intersection (signalized)

Adjusted bicycle and pedestrian ramp configuration for accessibility

Roadway alignment adjusted to accommodate gas line

One-way traffic on Park Blvd



Charleston Road – *Underpass*





Meadow Drive – Hybrid



Slip lane removed for improved bicycle safety

Emerson St

E. Meadow Dr

Alma St

Elevated railroad bridge

Lindero Dr


Protected bicycle lanes

Bike lane and column placement under railroad bridge to be refined

W. Meadow Dr




Meadow Drive – *Hybrid*





Track Shoofly

- A shoofly (temporary track) is **necessary** to construct the **Meadow Hybrid** grade separation
- Shoofly sequencing will allow for **reliable** and **consistent** Caltrain operations (with work windows)
- Opportunity to reduce **construction duration**





Temporary Track Extents



Total Project Cost Estimate

Rough Order of Magnitude (ROM)





Delivery Scenarios Evaluated

CHURCHILL
AVENUE
CROSSING

Churchill Avenue
with Seale Avenue

MEADOW AND
CHARLESTON
CROSSINGS

Concurrent

Charleston Road
+
Meadow Drive

Sequential

Charleston Road




Meadow Drive

Charleston Road
ONLY



Total Project Cost Estimate Life Cycle





Risk Associated with Costs*

Range of Estimate
Improves with
Design

15%
Current Design
Phase

35%
Design +
Environmental

65%
Design

Construction
Documents

✓ Risks Addressed/Mitigated

Stable project footprint identified

! Risks Remaining

Contractor procurement method not confirmed

Unknown utilities

Potential property impacts not confirmed

Soil and groundwater undefined

Construction sequencing uncertainty

Schedule and funding uncertainty

✓ Risks Addressed/Mitigated

Delivery method

Project footprint refined

! Risks Remaining

Utility relocations

Potential property acquisition

Railroad work windows

Construction staging

✓ Risks Addressed/Mitigated

Utilities located

Soil investigated

Potential property acquisitions appraised

! Risks Remaining

Market conditions

Regulatory approvals

Long-lead time materials

✓ Risks Addressed/Mitigated

Scope finalized

Utility design complete

Potential property acquired

Railroad windows confirmed

! Risks Remaining

Unforeseen conditions

Price increases before award



Cost and Schedule Tradeoffs

*Design development involves **balancing safety, access, rail operations, and community impact***

Considerations

Potential Constraint(s)

Maintain Vehicular Access During Construction

More complex staging and tighter work areas

Maintain High-Frequency Rail Operations

Focused work windows outside of peak period adjacent to rail

Minimize Project Footprint

Tighter work areas and more complex staging

Limit Noise During Construction

Reduced constructability and longer durations

Maintain Bicycle/Pedestrian Connections

Additional temporary detours and signage



Total Project Cost Estimate – Buildup



Construction Contractor Cost
(Direct & Indirect)
• *Permitting and Utilities*



Designer/Engineer of Record Costs



Agency Costs
(Caltrain, City, etc.)

- Project Management and Oversight
- Environmental Documentation and Permitting
- TASI (Operations)
- Construction Administration, Management, and Inspections



Real Property and Easements



Escalation
(Cost of Time)



Project Contingency
(Unknown & Known)



Basis of Total Project Cost Estimates

	Churchill Avenue with Seale Avenue	Charleston Road + Meadow Drive	Charleston Road	→ Meadow Drive	Charleston Road ONLY
Estimate Year (Year of Dollar)	2026				
Estimated Construction Start	2032				
Key Input of Cost	15% design				
High-Level Construction Duration	3 – 4 years	5 years	9 years		4 years



Churchill: Total Project Cost & Construction Duration

Delivery Scenario

**Churchill Avenue
with Seale Avenue**

*Construction
Duration*

3 – 4 years

*Total Project Cost
Estimate*

(Year of Expenditure)

\$420M – \$450M



Meadow/Charleston: Total Project Cost & Construction Duration

Delivery Scenario	Charleston Road + Meadow Drive	Charleston Road ↓ Meadow Drive	Charleston Road <i>ONLY</i>
Construction Duration	5 years	9 years	4 years
Total Project Cost Estimate (Year of Expenditure)	\$1B – 1.1B	\$1.2B – 1.3B	\$480M – 530M



Full Program (Churchill, Meadow, and Charleston)

Total Program Cost Estimate

Program Delivery Scenario	Total Program Cost Estimate
Churchill + Concurrent Meadow and Charleston	\$1.5B - \$1.6B
Churchill + Sequential Meadow and Charleston	\$1.7B - \$1.8B

Costs are preliminary in nature and represent rough order-of-magnitude estimates that will be further refined during future phases of design.



Anticipated Funding Sources

Project Phase	Funding Sources		
Planning & Conceptual Design	\$5M	City Capital Funds VTA Measure B Local Streets & Roads Fund	Phases fully funded Findings from design process will inform future City Council decisions surrounding prioritization, phasing, and implementation strategy
15% Design	\$20M	FRA Rail Crossing Elimination Grant	
35% Design		VTA Measure B Grade Separation Fund	
Final Design	\$9M	\$23.79M State TIRCP Award	Funding Strategy to be Determined
Construction		Potential Unallocated Funding: City Measure K: \$5M – \$30M VTA Measure B: \$325 – \$350M	



Environmental Documentation Process

Fall 2026

Environmental documentation runs in parallel with 35% Design

Fall 2027

Perform Technical Studies

Traffic, noise, air quality, biology, cultural resources, and related studies completed

Prepare Environmental Document

Findings documented for required determination level

Agency Review and Approval

Lead Agencies complete review and issue an environmental approvals

Caltrain Board approves CEQA document

FRA approves NEPA

Project Direction

City Council considers whether to authorize the project for implementation

CEQA: California Environmental Quality Act; **FRA:** Federal Railroad Administration; **NEPA:** National Environmental Policy Act



Approach to Potential Property Impacts

Possible Permanent Acquisition

Property or right-of-way that may be needed for the permanent improvements

Possible Temporary Construction Easements

Property access that may be needed during construction

WE ARE
HERE

Project is not approved or cleared for implementation; potential impacts are for planning purposes only.

15% Design

Identifies **preliminary project footprint** and **potentially affected parcels**

35% Design

Refines project and **construction limits** and **evaluates project changes** that could change potential property needs

Future Phases

Future acquisitions would require approval to advance the project into implementation and to follow Uniform Relocation Assistance and Real Property Acquisition Policies Act (URA).



Engagement

Community Meetings

15% design overview; Total Project Cost Estimate and schedule; community feedback opportunities; what will continue to be refined

8/25 & 8/26

PABAC

Bicycle and pedestrian elements of the grade separation project 15% design

9/3

City Council

Concurrence on concepts to advance into 35% design and environmental documentation

9/28

AUGUST

1

5

10

15

20

25

30

5

10

15

20

25

30

OCTOBER

8/20

CSTSC

New access routes for Palo Alto HS & other PAUSD schools

9/8

Rail Committee

Total Project Cost Estimate and schedule community meeting summary



FOR MORE INFORMATION

WWW.CALTRAIN.COM



3271